

N71 Skibbereen to Rosscarbery

The N71 Skibbereen to Rosscarbery Overlay Scheme consisted of road resurfacing & civil works on approximately 4km of carriageway of the N71 between Skibbereen Rosscarbery towns.

The contract was split into 5 individual sites over a distance of 20km.

The contract consisted of approximately 30,500m² of CI 942 resurfacing, 23,000m² of binder course resurfacing, 11,000m² of HRA resurfacing, 24,000m² of planning, 3000m² of road base resurfacing, 6400 Tonne of regulating, approx. 9km of hedge trimming and tree surgery, civil works including upgrade of drainage, french drains and service ducts within the site, 1600m³ of earthworks including excavation of soft spots and road widening, upgrading of traffic signs & road markings and installation of safety barrier at required locations.

